

Test BoQ

Test boq

Detail Bill of Quantities for Proposed Factory Building					
SECTION- A EARTHWORK AND SOLING					
ITEM NO.	DESCRIPTION	QTY	UNIT	RATE	AMOUNT
A-01	Earth work excavation for all type of work in all soils like black cotton soil, clay, sand, muroom, etc but other than soft and hard rock including shoring, strutting and dewatering wherever required, scaffolding and stacking the excavated materials within 50 meters, all complete as per specifications.				
	a) From average ground level up to 1.50 M depth.	1250	Cu.m.	100	1,25,000
	b) Below 1.5M up to 3.0M depth	1250	Cu.m.	110	1,37,500
	c) Below 3.0M up to 4.5M depth	50	Cu.m.	140	7,000
	d) Below 4.5M up to 6.0M depth	170	Cu.m.	180	30,600
A-02	Filling in plinth and backfilling foundations with approved materials including spreading in 150mm layers, watering, ramming, compacting, with suitable vibro roller or earth compactor wherever applicable as decided by the Engineer, leveling, etc. complete. (Measurements for compacted volume of space occupied by filling based on certified excavation dimensions)				
	a) With selected earth available from Excavation.				
	i) Within Plant Boundary	410	Cu.m.	85	34,850
	b) With selected earth brought from outside having PI value less than 6	QRO	Cu.m.	530	
	c) With approved Sand brought from Outside.	QRO	Cu.m.	1230	
	d) With approved Quarry Dust brought from Outside.	QRO	Cu.m.	850	